



**PROJECT:** 88 Cavendish Road  
**SYSTEM:** 1  
**Indoor Units :** 8 of 20  
**Capacity :** 14.5 of 12 (120.83 %)  
**Total Pipe** 48.7 of 300m  
**Actual Cooling (Tot/Sens)** 29.30 kW / 21.77 kW  
**Required Cooling (Tot/Sens)** 24.50 kW / ?  
**Total Heating** 37.31 kW  
**Required Heating** ?  
**Building Diversity (Clg)** 0 %  
**Building Diversity (Htg)** 0 %  
 (? = Incomplete information)

1. It is the responsibility of the consultant or contractor, to verify and confirm that the equipment selection and system design is correct before installation.

2. The above schematic, which has been designed by the user, is a diagrammatic representation of a Super Modular Multi system and is not to scale.

3. Please note that in the event of future system expansion being allowed for in the system design or a change in cooling/heating requirements, a re-evaluation of the air conditioning systems must be made prior to final installation.

